KOLAR DIVISION.

Dated 19th August 1906.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 15th September 1906 for restoring Seethahalli tank, Registered No. 362 of Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1970.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates tendered should include royalty on stones, etc., removed from the Government lands, to be paid to the Government :—

4. Each tender must be accompanied by a deposit of Rs. 150-0-0 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Seethahalli tank Registered No. 362 of Malur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineeer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Item of work.	*Per.*	*Quantity.*
Bund—		
Earthwork	C. yd.	26,458
Old stone work	Do	91
New stone work	Do	634
Gravel backing	Do	483
Grade stones	No.	19
B. M. Stones	„	2
Date stones	„	1
Tank No. stone	„	1
Gauge stone	„	1
Turfing	Sq. yd.	5,408
Clearing sand in the breaches	Lump sum	
Puddle walls at breaches including baling charges	Lump sum	
Weir, left, 200 feet long with 12-feet returns—		
Earthwork	C. yd.	685
Brick in surki mortar	Cft.	1,983
Plastering with chunam	Sq. yd.	16·16
Burnt stone slabes	Sq. ft.	332
Right weir 100 feet length with 12-feet returns	Lump sum rupees	

K. KRISHNAIENGAR,
Executive Engineer.